



Cross Reference RA Part Number PN-272396



Model: TS 873A0800A2CN7GKKAA

800A 3Pole 347/600V 3 Phase (4 Wire) 60 Hz Automatic Transfer Switch c/w

Manually Initiated Electrically Operated Transfer Switch c/w
Source Selector Switch
Position Indicating Lights
Source Available Lights
No Controller Required
Auxiliary Contact - Generator Side
Auxiliary Contact - Utility Side
Generator Power Available Contact
Utility Power Available Contact
Open Style (No Enclosure)
Drawings/Programming Sheets
O & M Manual

SITE STARTUP & COMMISSIONING

Single trip - for site startup at Waterloo , Ontario includes single trip - half day

Regular hours labor , travel time and mileage.

Additional site days or site visits if required it would be charged at Thomson Technology field service rates.

Thomson Technician standard field service rates i.e Thomson Per diem rates.

Per Diem Rate** - \$1500.00/Day

Stand-By Rat - \$1250.00/Day

Travel Time - \$1050.00/Day

Plus Travel & living expense at cost plus 15%

Per Diem Rates - 10-hour work day / OT-\$210/ Hr.

MISCELLANEOUS SERVICE CHARGES 675.00 675.00

Single trip - for site startup at Waterloo , Ontario includes single trip - two regular hours labor , travel time and mileage.

Additional site days or site visits if required it would be charged at Thomson Technology field service rates.

Thomson Technician standard field service rates i.e Thomson Per diem rates.

Per Diem Rate** - \$1500.00/Day

Stand-By Rat - \$1250.00/Day

Travel Time - \$1050.00/Day

Plus Travel & living expense at cost plus 15%

Per Diem Rates - 10-hour work day / OT-\$210/ Hr.

Additional Quote Information:

Approximate an overall dimensions of an open style transfer switch - 29.96"(W) X 24.813"(H) X 12.73"(D).

Para 2.2 - Proposed electrically operated manual transfer switch.

Para 2.4.3 - Neutral position is not possible due to manual transfer.

Para 2.4.4 - Proposed manual transfer switch does not have any ground fault.

Para 2.7 - Proposed an open style TS, house in MCC enclosure.

Para 3.2 - Price for installation is not included.

If you have any query, please feel free to contact us.

Regards,

Thomson Technology Standard Factory Testing - is included .

- Site Start-up and Commissioning is NOT included .

- Standard 1 Year Factory Warranty Included .

- Standard Lugs Included .

QUOTE: Q-119718